

System Overview

- 1. **Locker Series:** Express
- 2. **Installation Type:** Linear
- 3. **Color Finish:** tbd
- 4. **Total Package Lockers:** 16
- 5. **Total Dry Cleaning Lockers:** 0


Site Preparation Requirements (Provided by Others):

- 1. Electrical and Internet outlets must be installed with bottom of the faceplates at 81" FFF. If outlets are surface mounted, bottom of faceplates must be at 82.5" FFF.
- 2. System dimensions shown above should be verified in the field to confirm the system fits within the desired space
- 3. Each locker module has a typical dimension tolerance of +/- 1/8"
- 4. Actual Locker Height is: 81" - 82-1/4" (range due to adjustable leveling feet)
- 5. Actual Locker Depth is: 22-3/4"
- 6. If the system will be recessed and trimmed in, all finished trim must be completed after installation

Module/Tower Count	
Module	Qty.
EXEM04A	0
EXEM08A	0
EXEM09A	0
EXEM10A	0
EXEM13A	0
EXEM16A	1
EXEK12A-PC	0
EXEM04A-DCL	0
Total:	1

Locker Compartment Information (inches)				
Type	Qty.	Height	Width	Depth
1-High	10	4.8	13.5	22.5
2-High	4	10.2		
3-High	2	15.6		
4-High	0	21.0		
5-High	0	26.4		
6-High	0	31.8		
D6-High	0	31.8		
Total:	16			

DO NOT SCALE OFF THIS DRAWING

ELEVATION: Front View / Profile Elevation 1			
PROJECT NAME: Product Cutsheet		DRAWN BY: Package Concierge	
CREATED: 08/23/2019	LOCATION: Manhattan ,KS	 packageconciierge.com <small>Manufactured by Florence Corporation</small>	
INSTALL BY: N/A	REFERENCE NO:		
DRAWING NO. EXEM16ACS	SHEET 1		
APPROVED SIGNATURE:		PRINTED NAME/DATE:	