



System Overview

1. Locker Series: Element Indoor

- 2. Installation Type: Linear
- 3. Color Finish: tbd
- 4. Total Package Lockers: 11
- 5. Total Dry Cleaning Lockers: 0

Site Preparation Requirements (Provided by Others):

1. Electrical and Internet outlets must be installed with bottom of the faceplates at 83" FFF. If outlets are surface mounted, bottom of faceplates must be at 84.5" FFF.

2. System dimensions shown above should be verified in the field to confirm the system fits within the desired space

3. Each locker module has a typical dimension tolerance of +/- 1/8"

4. Actual Locker Height is: 82-1/4" - 83-3/4" (range due to adjustable leveling feet)

5. Actual Locker Depth is: 23-7/8"

6. If the system will be recessed and trimmed in, all finished trim must be completed after installation

	Module/Tov	Module/Tower Count		ker Compa	artment Info	mation (ind	ches)	ELEVATION: Front View / Profile Elevation 1		
	Module	Qty.	Туре	Qty.	Height	Width	Depth	1	·	
S	ELIM04A	0	1-High	6	4.8	13.5	22.5	1		
	ELIM08A	0	2-High	2	10.2			PROJECT NAME: Product Cutsheet		DRAWN BY: Package Concierge
	ELIM09A	0	3-High	2	15.6					
	ELIM10A	0	4-High	1	21.0			CREATED: 08/23/2019	LOCATION: Manhattan ,KS	PACKAGE CONCIERGE
	ELIM13A	0	5-High	0	26.4					
	ELIM16A	0	6-High	0	31.8			INSTALL BY: N/A	REFERENCE NO:	
	ELIK11A-PC	1	D6-High	0	31.8					packageconcierge.com
	ELIM04A-DCL	0	Total:	11				DRAWING NO.	SHEET 1	
	Total:	1		-				ELIK11A-PCCS		Manufactured by Florence Corporation
n	DO NOT SCALE OFF THIS DRAWING							APPROVED SIGNATURE:		PRINTED NAME/DATE:

