



System Overview

1. Locker Series: Element Indoor

2. Installation Type: Linear

3. Color Finish: tbd

4. Total Package Lockers: 0

5. Total Dry Cleaning Lockers: 4

Site Preparation Requirements (Provided by Others):

- 1. Electrical and Internet outlets must be installed with bottom of the faceplates at 83" FFF. If outlets are surface mounted, bottom of faceplates must be at 84.5" FFF.
- **2.** System dimensions shown above should be verified in the field to confirm the system fits within the desired space
- 3. Each locker module has a typical dimension tolerance of +/- 1/8"
- 4. Actual Locker Height is: 82-1/4" 83-3/4" (range due to adjustable leveling feet)
- 5. Actual Locker Depth is: 23-7/8"
- 6. If the system will be recessed and trimmed in, all finished trim must be completed after installation

Module/Tower Count			
Module	Qty.		
ELIM04A	0		
ELIM08A	0		
ELIM09A	0		
ELIM10A	0		
ELIM13A	0		
ELIM16A	0		
ELIK11A-PC	0		
ELIM04A-DCL	1		
Total:	1		

unt	Loc	Locker Compartment Information (inches)					
y.	Туре	Qty.	Height	Width	Depth		
١	1-High	0	4.8				
)	2-High	0	10.2				
)	3-High	0	15.6				
١	4-High	0	21.0	13.5	22.5		
)	5-High	0	26.4				
)	6-High	0	31.8				
)	D6-High	4	31.8				
	Total:	4					

DO NOT SCALE OFF THIS DRAWING

ELEVATION: Front View / Profile Elevation 1					
PROJECT NAME: Pro	DRAWN BY: Package Concierge				
CREATED: 08/23/2019	LOCATION: Manhattan ,KS	PACKAGE CONCIERGE			
INSTALL BY: N/A	REFERENCE NO:	packageconcierge.com			
DRAWING NO. ELIM04A-DCLCS	SHEET 1	Manufactured by Florence Corporatio			
APPROVED SIGNATURE:		PRINTED NAME/DATE:			