



System Overview

1. Locker Series: Element Indoor

2. Installation Type: Linear

3. Color Finish: tbd

4. Total Package Lockers: 10

5. Total Dry Cleaning Lockers: 0

Site Preparation Requirements (Provided by Others):

- 1. Electrical and Internet outlets must be installed with bottom of the faceplates at 83" FFF. If outlets are surface mounted, bottom of faceplates must be at 84.5" FFF.
- **2.** System dimensions shown above should be verified in the field to confirm the system fits within the desired space
- 3. Each locker module has a typical dimension tolerance of +/- 1/8"
- 4. Actual Locker Height is: 82-1/4" 83-3/4" (range due to adjustable leveling feet)
- 5. Actual Locker Depth is: 23-7/8"
- 6. If the system will be recessed and trimmed in, all finished trim must be completed after installation

M. 1.17.						
Module/10	Module/Tower Count					
Module	Qty.					
ELIM04A	0					
ELIM08A	0					
ELIM09A	0					
ELIM10A	1					
ELIM13A	0					
ELIM16A	0					
ELIK11A-PC	0					
ELIM04A-DCL	0					
Total:	1					

					•		
Qty.	Туре	Qty.	Height	Width	Depth		
0	1-High	0	4.8				
0	2-High	8	10.2				
0	3-High	1	15.6				
1	4-High	0	21.0	13.5	22.5		
0	5-High	1	26.4				
0	6-High	0	31.8				
0	D6-High	0	31.8				
0	Total:	10			·		
1			_	•			

Locker Compartment Information (inches)

DO NOT SCALE OFF THIS DRAWING

	ELEVATION: Front View / Profile Elevation 1							
	PROJECT NAME: Product Cutsheet			DRAWN BY: Package Concierge				
	CREATED: 08/23/2019	LOCATION: Manhattan ,KS		■ PACKAGE ■ CONCIERGE				
	INSTALL BY: N/A	REFERENCE NO:	pa	ckageconcierge.com				
	DRAWING NO. ELIM10ACS	SHEET 1	Manu	ufactured by Florence Corporation				
	APPROVED SIGNATURE:		PRII	NTED NAME/DATE:				