

System Overview

1. Locker Series: Element Outdoor w/ Light Awning

2. Installation Type: Linear

3. Color Finish: tbd

4. Total Package Lockers: 16

5. Total Dry Cleaning Lockers: 0

- Site Preparation Requirements (Provided by Others):


 1. Electrical and Internet junction boxes must be installed with bottom of the junction box at 87" FFF
- junction boxes must be surface mounted
- 2. System dimensions shown should be verified in the field to confirm the system fits within the
- 3. Each locker module has a typical dimension tolerance of +/- 1/8"
- 4. Actual Locker Height is: 85-1/2" 87" (range due to adjustable leveling feet)
- 5. Actual Locker Depth is: 34"


Module/Tower Count				
Module	Qty.			
ELOM04A-LT	0			
ELOM08A-LT	0			
ELOM09A-LT	0			
ELOM10A-LT	0			
ELOM13A-LT	0			
ELOM16A-LT	1			
ELOK11A-PC- LT	0			
ELOM04A- DCL-LT	0			
Total:	1			

er Count	Locker Compartment Information (inches)				
Qty.	Туре	Qty.	Height	Width	Depth
0	1-High	10	4.8		
0	2-High	4	10.2		
0	3-High	2	15.6		
0	4-High	0	21.0	13.5	22.5
0	5-High	0	26.4		
1	6-High	0	31.8		
0	D6-High	0	31.8		
	Total:	16			
0					

DO NOT SCALE OFF THIS DRAWING

J	ELEVATION: Front View / Profile Elevation 1				
l	PROJECT NAME: Product Cutsheet			DRAWN BY: Package Concierge	
	CREATED: 08/23/2019	LOCATION: Manhattan ,KS		■ PACKAGE ■ CONCIERGE	
	INSTALL BY: N/A	REFERENCE NO:	pa	ckageconcierge.com	
	DRAWING NO. ELOM16A-LTCS	SHEET 1	Manu	ufactured by Florence Corporation	
1	APPROVED SIGNATURE:		PRI	NTED NAME/DATE:	





System Overview

1. Locker Series: Element Outdoor

2. Installation Type: Linear

3. Color Finish: tbd

4. Total Package Lockers: 16 5. Total Dry Cleaning Lockers: 0

- Site Preparation Requirements (Provided by Others):

 1. Electrical and Internet junction boxes must be installed with bottom of the junction box at 87" FFF
- junction boxes must be surface mounted
- 2. System dimensions shown should be verified in the field to confirm the system fits within the
- 3. Each locker module has a typical dimension tolerance of +/- 1/8"
- 4. Actual Locker Height is: 82-1/4" 83-3/4" (range due to adjustable leveling feet)
- 5. Actual Locker Depth is: 23-7/8"

Module/Tower Count			
Module	Qty.		
ELOM04A	0		
ELOM08A	0		
ELOM09A	0		
ELOM10A	0		
ELOM13A	0		
ELOM16A	1		
ELOK11A-PC	0		
ELOM04A- DCL	0		
Total:	1		

Count	Dunt Locker Compartment Information (inches)				hes)
Qty.	Туре	Qty.	Height	Width	Depth
0	1-High	10	4.8		
0	2-High	4	10.2		
0	3-High	2	15.6		
0	4-High	0	21.0	13.5	22.5
0	5-High	0	26.4		
1	6-High	0	31.8		
0	D6-High	0	31.8		
0	Total:	16			

DO NOT SCALE OFF THIS DRAWING

ELEVATION: Front View / Profile Elevation 1				
PROJECT NAME: Product Cutsheet			DRAWN BY: Package Concierge	
CREATED: 08/23/2019	LOCATION: Manhattan ,KS		■ PACKAGE ■ CONCIERGE	
INSTALL BY: N/A	REFERENCE NO:	pa	ckageconcierge.com	
ELOM16ACS	SHEET 2	Manu	Ifactured by Florence Corporation	
APPROVED SIGNATURE:		PRIN	NTED NAME/DATE:	