

## System Overview

1. Locker Series: Express

2. Installation Type: Linear

3. Color Finish: tbd

4. Total Package Lockers: 9

5. Total Dry Cleaning Lockers: 0

## Site Preparation Requirements (Provided by Others):

1. Electrical and Internet outlets must be installed with bottom of the faceplates at 81" FFF. If outlets are surface mounted, bottom of faceplates must be at 82.5" FFF.

2. System dimensions shown above should be verified in the field to confirm the system fits within the desired space

3. Each locker module has a typical dimension tolerance of +/- 1/8"

**4.** Actual Locker Height is: 81" - 82-1/4" (range due to adjustable leveling feet)

5. Actual Locker Depth is: 22-3/4"

6. If the system will be recessed and trimmed in, all finished trim must be completed after installation

	Module/Tower Count		Locker Compartment Information (inches)					ELEVATION: Front Vie
	Module	Qty.	Туре	Qty.	Height	Width	Depth	1
S	EXEM04A	0	1-High	3	4.8	13.5	22.5	PROJECT NAME: Prod
	EXEM08A	0	2-High	3	10.2			
	EXEM09A	1	3-High	1	15.6			
	EXEM10A	0	4-High	0	21.0			<b>CREATED:</b> 08/23/2019
	EXEM13A	0	5-High	0	26.4			
	EXEM16A	0	6-High	2	31.8			INSTALL BY: N/A
	EXEK12A-PC	0	D6-High	0	31.8			
	EXEM04A- DCL	0	Total:	9				DRAWING NO. EXEM09ACS
	Total:	1						
on I	DO NOT SCALE OFF THIS DRAWING							APPROVED SIGNATURE:

