

System Overview

1. **Locker Series:** Express
2. **Installation Type:** Linear
3. **Color Finish:** tbd
4. **Total Package Lockers:** 10
5. **Total Dry Cleaning Lockers:** 0


Site Preparation Requirements (Provided by Others):

1. Electrical and Internet outlets must be installed with bottom of the faceplates at 81" FFF. If outlets are surface mounted, bottom of faceplates must be at 82.5" FFF.
2. System dimensions shown above should be verified in the field to confirm the system fits within the desired space
3. Each locker module has a typical dimension tolerance of +/- 1/8"
4. Actual Locker Height is: 81" - 82-1/4" (range due to adjustable leveling feet)
5. Actual Locker Depth is: 22-3/4"
6. If the system will be recessed and trimmed in, all finished trim must be completed after installation

Module/Tower Count	
Module	Qty.
EXEM04A	0
EXEM08A	0
EXEM09A	0
EXEM10A	1
EXEM13A	0
EXEM16A	0
EXEK12A-PC	0
EXEM04A-DCL	0
Total:	1

Locker Compartment Information (inches)				
Type	Qty.	Height	Width	Depth
1-High	0	4.8	13.5	22.5
2-High	8	10.2		
3-High	1	15.6		
4-High	0	21.0		
5-High	1	26.4		
6-High	0	31.8		
D6-High	0	31.8		
Total:	10			

DO NOT SCALE OFF THIS DRAWING

ELEVATION: Front View / Profile Elevation 1			
PROJECT NAME: Product Cutsheet		DRAWN BY: Package Concierge	
CREATED: 08/23/2019	LOCATION: Manhattan ,KS	 packageconciierge.com <small>Manufactured by Florence Corporation</small>	
INSTALL BY: N/A	REFERENCE NO:		
DRAWING NO. EXEM10ACS	SHEET 1		
APPROVED SIGNATURE:		PRINTED NAME/DATE:	